



श्यामा प्रसाद मुखर्जी महिला महाविद्यालय SHYAMA PRASAD MUKHERJI COLLEGE FOR WOMEN



दिल्ली विश्वविद्यालय University of Delhi

पंजाबी बाग (पश्चिम), नई दिल्ली-110026 PUNJABI BAGH (West), New Delhi-110026

दूरभाष Phone : 25224499, फैक्स Fax : 25221672

E-mail : spmcollegedu@gmail.com Website : http://spm.du.ac.in

संदर्भ सं. Ref. No. 98/SPMC/Admn./Quotations/Misc/2018/1110

दिनांक Dated 4/1/2019

NOTICE INVITING QUOTATION


SPM College invites sealed quotations for the "repair / laying & shifting of water pipe line at staff quarters" of the college. The last date for submitting the quotation is Monday 7th January 2019.

S.no.	Item	Qty.	Unit	Rate	Amount
P.77/ 2.10	Excavating trenches of required width for pipes, cables etc including excavation for sockets, an dressing of sides, ramming of bottoms, depth upto 1.5m including getting out the excavated soil, and then returning the soil as required, in layers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming watering etc. and disposing of surplus excavated soil as directed, within a lead of 50 m:				
P.77/ 2.10.1.1	Pipes, Cables etc, not exceeding 80 mm dia	90	mtr		
P.75/ 2.25	Filling available excavated earth (excluding rock) in trenches, plnth sides of foundations etc. in layers not exceeding 20 cm in depth consolidating each deposited layer by rammig and watering, lead up to 50 m and lift 1.5m	6	cum		
P.85/ 4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shittering- All work up to plinth level:				
P.85/ 4.1.5	1:3:6 (1 cement : 3 coarse sand (zone-III) : 6 graded stone aggregate 20 mm nominal size	1	cum		
P.312/ 18.9	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pies & fittings with one step CPVC solvent cement, trenching, reffling & testing of joints complete as per direction of Engineer in Charge.				
P.312/ 18.9.6	50 mm nominal outer dia Pipes	90	mtr		

P.312/ 18.9.2	20 mm nominal outer dia Pipes	45	mtr		
P.314/ 18.18	Providing and fixing ball valve (brass) of approved quality, High or low pressure, with plastic floats complete:				
P.314/ 18.18.2	20 mm nominal bore	6	mtr		
P.314/ 18.17	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end):				
P.314/ 18.17.1A	20 mm nominal bore	2	Nos.		
P.314/ 18.17.4	50 mm nominal bore	2	Nos.		
P.330/ 18.32	Constructing masonry Chamber 30x30x50 cm inside, in brick work in cement mortar 1:4 (1 cement : 4 coarse sand) for stop cock, with C.I. surface box 100x100x75 mm (inside) with hinged cover fixed in cement concrete slab 1:2:4 mix (1 cement :2 coarse sand : 4 graded stone aggregate 20 mm nominal size), i/c necessary excavation , foundation concrete 1:5:10 (1 cement : 5 fine sand: 10 graded stone aggregate 40 mm nominal size) and inside plastering with cement mortar 1:3 (1 cement : 3 coarse sand) 12 mm thick, finished with al floating with a floating coat of neat cement complete as per standard design:				
P.330/ 18.32.1	With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	2	each		
EX-1	Removal of malba at site	1	job		
EX-2	Road cutting RCC road and Re-laying of road (length 6mtr and depth 200 mm)	1	job		
TOTAL					

Terms and Conditions :

1. Your rates must be mentioned with GST and other charges if any.
2. You have to complete the work within two weeks of receipt of work order.
3. Quotation envelop should be sealed and super-scribed as '**Quotation for repair / laying & shifting of water pipe line at staff quarters**'
4. The payment shall be released as per the actual measurement.
5. The quantities can be increased or decreased according to requirements.
6. No advance will be given.
7. Please send your quotation by post or by hand
8. Right of acceptance of any quoted rates is reserved with the undersigned.
9. Your quotation rates will be valid for one year from the date of opening.


 Dr. Sadhna Sharma
 Principal (Officiating)