

SHYAMA PRASAD MUKHERJI COLLEGE FOR WOMEN  
Punjabi Bagh (W), New Delhi – 110026

SPM C/2020/1858A

4<sup>th</sup> March 2020

TENDER NOTICE

Sealed quotations are hereby invited from the contractors enlisted with C.P.W.D., MES, Railway and working contractors of Delhi University for the following work, so as to reach the office of the undersigned upto 1:00 p.m. on 24.3.2020.

1. Description of work : Civil Repair work in room no. 59 and 60
2. Site of work Scope of work : SPM College

ESTIMATE					
Name of work : Repair of room no 59 and 60 .					
S.NO	ITEMS	QTY	UNIT	RATE	AMOUNT
1	Providing and fixing APP (Atactic Polypropylene Polymer) modified prefabricated five layer 2 mm thick water proofing membrane , black finished reinforced with glass fibre matt consisting of a coat of bitumen primer for bitumen membrane @ 0.40 litre/sqm by the same membrane manufacture of density at 25°C, 0.87 - 0.89 kg/ litre and viscosity 70 - 160 cps. Over the primer coat the layer of membrane shall be laid using Butane torch and sealing all joints etc., and preparing the surface complete. The vital physical and chemical parameters of the membrane shall be as under : Joint strength in longitudinal and transverse direction at 23°C as 350/300 N/ 5 cm. Tear strength in longitudinal and transverse direction as 60/80N. Softening point of membrane not less than 150°C. Cold flexibility shall be upto -2°C when tested in accordance with ASTM, D - 5147. The laying of membrane shall be got done through the authorized applicator of the manufacture of membrane. 14.89.1 2mm (for corrugated roof sheets) .	110	Sqm		



2	Providing and fixing false ceiling at all height including including fixing of gypsum board to ceiling section and perimeter channel with the help of dry wall screws of size 3.5 x 25 mm at 230 mm c/c, including jointing and finishing to a flush finish of tapered and square edges of the board with recommended jointing compound , jointing tapes , finishing with jointing compound in 3 layers covering upto 150 mm on both sides of joint and two coats of primer suitable for board, all as per manufacturer's specification and also including the cost of making openings for light fittings, grills, diffusers, cutouts made with frame of perimeter channels suitably fixed, all complete as per drawings, specification and direction of the Engineer in Charge but excluding the cost of painting with : 12.45.1 12.5 mm thick tapered edge gypsum plain board conforming to IS: 2095- (Part I) : 2011 (Board with BIS certification marks) .	100	Sqm		
3	12 mm cement plaster of mix : 13.1.2 1:6 (1 cement: 6 fine sand)	84	Sqm		
4	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead. sqm	84	Sqm		
5	Providing and fixing Dr fixit water proofing chemical treatment	84	Sqm		
6	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade : 13.41.1 New work (two or more coats) over and including water thinnable priming coat with cement primer	250	Sqm		
	TOTAL				

**Terms and Conditions:-**

1. The Contractor shall quote rates with GST, No extra GST shall be paid to the Contractor.
2. Compensation for delay of work @1.5% per month of delay to be computed on per day basis and levied on the contractor on delay of work.
3. Labour laws are to be complied by the contractor. The contractor shall obtain a valid license under the Contract Labour (R&A) Act 1970 and the contract labour (Regulation and Abolition) Central Rules 1971 before the commencement of work and continue to have a valid license until the completion of work. The contractor shall also abide by the provisions of the Child Labour Act 1986.
4. The contractors / firms are advised to inspect the site, examine the drawings and make all investigations regarding the extent of work, its scope and conditions under which the work is to be executed. No claim for any extra payments of any kind on account of lack of information about the site conditions shall be entertained.
5. The rates shall be quoted both in figures and words





6. The contractor / firm may be required to produce documents regarding partnership and / or Articles of Association of the Company along with the tender document.
7. The offer shall remain open for a period of 60 days from the stipulated date of submission of quotation.
8. The Owner reserves the right to reject any or all of the quotations, either in whole or in part, without assigning any reason for so doing.

*Sadhna*

Dr. Sadhna Sharma  
Principal(Officiating)

