

SHYAMA PRASAD MUKHERJI COLLEGE FOR WOMEN
Punjabi Bagh (W), New Delhi – 110026

4th March 2020


TENDER NOTICE

Sealed quotations are hereby invited from the contractors enlisted with C.P.W.D., MES, Railway and working contractors of Delhi University for the following work, so as to reach the office of the undersigned upto 1:00 p.m. on 24.3.2020.

1. Description of work : Repair of renovation room no. 18 and 19
2. Site of work : SPM College for Women
3. Scope of Work : Estimate attached

Terms and Conditions:-

1. The Contractor shall quote rates with GST, No extra GST shall be paid to the Contractor.
2. Compensation for delay of work @1.5% per month of delay to be computed on per day basis and levied on the contractor on delay of work.
3. Labour laws are to be complied by the contractor. The contractor shall obtain a valid license under the Contract Labour (R&A) Act 1970 and the contract labour (Regulation and Abolition) Central Rules 1971 before the commencement of work and continue to have a valid license until the completion of work. The contractor shall also abide by the provisions of the Child Labour Act 1986.
4. The contractors / firms are advised to inspect the site, examine the drawings and make all investigations regarding the extent of work, its scope and conditions under which the work is to be executed. No claim for any extra payments of any kind on account of lack of information about the site conditions shall be entertained.
5. The rates shall be quoted both in figures and words
6. The contractor / firm may be required to produce documents regarding partnership and / or Articles of Association of the Company along with the tender document.
8. The offer shall remain open for a period of 60 days from the stipulated date of submission of quotation.
9. The Owner reserves the right to reject any or all of the quotations, either in whole or in part, without assigning any reason for so doing.


Dr. Sadhna Sharma
Principal(Officiating)

Enclosed : Estimate and scope of work for Repair and renovation room no. 18 & 19

Name of work : Repair of renovation room no.18 & 19


S. No.	Item	Qty.	Unit	Rate	Amount
1	13.1 12 mm cement plaster of mix : 13.1.1 1:4 (1 cement: 4 fine sand)	80	Sqm.		
2	13.41 Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade : 13.41.1 New work (two or more coats) over and including water thinnable priming coat with cement primer sqm 93.70	200	Sqm.		
3	13.80 Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete. sqm 87.35	200	Sqm.		
4	15.7 Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. 15.7.4 In cement mortar cum 842.75	3	Cum		
5	15.56 Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead. sqm 22.40	80	Sqm.		
6	14.46 Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete. sqm 10.80	200	Sqm.		
7	6.4 Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : 6.4.2 Cement mortar 1:6 (1 cement : 6 coarse sand) cum 5582.85	1	Cum		
8	4.1 Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 4.1.3 "1:2:4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size). cum 5481.95	0.7	Cum		
9	2.25 Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m. cum 125.75	1	Cum		

Sadhuraj

Principal

Shyama Prasad Mukherji College
(University of Delhi)
Punjabi Bagh (West)
New Delhi-110026

10	9.20 Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) decorative type, core of block board construction with frame of 1st class hard wood and well matched teak 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters. 9.20.1 35 mm thick including ISI marked Stainless Steel butt hinges with necessary screws sqm 2488.95	6	Sqm.		
11	11.26 Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) : 11.26.1 25 mm thick sqm 1158.10	55	Sqm.		
12	12.41 Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes. 12.41.1 75 mm diameter metre 148.75	18	Mtr.		
13	Providing & applying tape-create Coating (Dr. fixit)	75	Sqm.		
14	Providing new door opening in wall Demolishing Brick work, Dismantling old window, etc complete.	1	Job		
	Total				
	GST @ 18%				
	Grand Total				


Sadhna
 Principal
 Shyama Prasad Mukherji College
 (University of Delhi)
 Punjabi Bagh (West)
 New Delhi-110026