

क्रमांक / Ref. SPMC(2023)1058दिनांक / Dated 11/9/2023**Notice Inviting Quotation**

Sealed quotations are invited from the civil working contractors of the College/ CPWD/ Delhi University.
"Restoration work in class rooms (Room no-56,57,62).

Publishing Date	01/09/2023
Estimated Cost	2,47,271/-
Completion Time	40 Days
Last date for Submission of Quotation	22/09/2023 by 3.00 pm

Following are the General Conditions of the Quotation:-

1. Rates quoted should be inclusive of taxes.
2. 1 % water and electricity charges will be recovered from the bill.
3. 1 % Labour and 2% TDS charges will be deducted from the bill.
4. 5% of the bill will be retained as security deposit and shall be returned after successful completion of work.
5. Compensation for delay of work @ 1.5% per month of delay to be computed on per day basis. Provided that total amount of compensation for delay to be paid under this condition shall not exceed 10% of the Value of work or to the Value of the item or group of work for which a separate period of completion is originally given.
6. The Firm/company should read all the instructions, nomenclature of items, specifications etc. contained in the tender documents very carefully, before quoting the rates.
7. For general rules and direction, conditions of contract, the tenderer shall refer to "CPWD General Conditions of contract – 2014." except for exceptions mentioned in this document, which will form a part of the Agreement with up to date correction slips.
8. Firm/Company may download the quotation form from the college website i.e. <http://spm.du.ac.in> or may obtain from the college on all the working days between 10 am to 3 pm
9. The quotation should be sealed cover & super scribed with the words "Quotation Restoration work in class rooms no-56,57,62" and should reach at Shyama Prasad Mukherji College for women, Road no 57 west Punjabi bagh, New delhi-110026 by hand on or before 22/09/2023 by 3.00 pm
10. The undersigned has the right to increase or decrease the quantity of all or any items and also reserve the right to cancel the quotation at any time.

Sadhna
Principal

SHYAMA PRASAD MUKHERJI COLLEGE FOR WOMEN**Bills of Quantity****Restoration work in class rooms (Room no-56,57,62)**

S.NO	ITEMS	QTY	UNIT	RATE	AMOUNT
1	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position with c.c 1:2:4 and applying a priming coat of approved steel primer all complete. (use ISMB200)	825	Kg		
2	Providing gola 75x75 mm in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 stone aggregate 10 mm and down gauge), including finishing with cement mortar 1:3 (1 cement : 3 fine sand) as per standard design : 12.21.1 In 75x75 mm deep chase metre	80	Mtr		
3	Making khurras 45x45 cm with average minimum thickness of 5 cm cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate of 20 mm nominal size) over P.V.C. sheet 1 m x1 m x 400 micron, finished with 12 mm cement plaster 1:3 (1 cement : 3 coarse sand) and a coat of neat cement, rounding the edges and making and finishing the outlet complete. each	12	Each		
4	Demolishing brick tile covering in terracing including stacking (demolishing carefully and stacking at site for re-use) of serviceable material and disposal of unserviceable material within 50 metres lead. sqm 86.80	130	Sqm		
5	Demolishing mud phaska in terracing and disposal of material (stacking at site for re-use) within 50 metres lead. cum 753.75	20	Cum		

6	Re-fixing and laying 10 cm thick (average) mud phaska of damped brick earth on roofs laid to slope consolidated and plastered with 25 mm thick mud mortar mixed with bhusa @ 35 kg per cum of earth and gobri leaping with mix 1:1 (1 clay : 1 cow dung) and covered with flat tile bricks (OLD TILES USED), grouted with cement mortar 1:3 (1 cement : 3 fine sand) mixed with 2% of integral water proofing compound by weight of cement and finished neat.	130	Sqm		
7	Providing and fixing Dr fixit chemical coating URP 301 mix with cement. The surface clean with fresh water and apply chemical coating.	130	Sqm		
8	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 4.1.3 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources) .	0.5	Cum		

Sadhna
PRINCIPAL