

क्रमांक / Ref. SPMC/2023/1031A

दिनांक / Dated.....29/8/2023


**Notice Inviting Quotation**

Sealed quotations are invited from the civil working contractors of the College/ CPWD/ Delhi University.  
"Repair and renovation in Room no-60,61,64,65,58,55.

Publishing Date	29/08/2023
Estimated Cost	2,51,406/-
Completion Time	30 Days
Last date for Submission of Quotation	20/09/2023 by 3.00 pm

**Following are the General Conditions of the Quotation:-**

11. Rates quoted should be inclusive of taxes.
12. 1 % water and electricity charges will be recovered from the bill.
13. 1 % Labour and 2% TDS charges will be deducted from the bill.
14. 5% of the bill will be retained as security deposit and shall be returned after successful completion of work.
15. Compensation for delay of work @ 1.5% per month of delay to be computed on per day basis. Provided that total amount of compensation for delay to be paid under this condition shall not exceed 10% of the Value of work or to the Value of the item or group of work for which a separate period of completion is originally given.
16. The Firm/company should read all the instructions, nomenclature of items, specifications etc. contained in the tender documents very carefully, before quoting the rates.
17. For general rules and direction, conditions of contract, the tenderer shall refer to "CPWD General Conditions of contract – 2014." except for exceptions mentioned in this document, which will form a part of the Agreement with up to date correction slips.
18. Firm/Company may download the quotation form from the college website i.e. <http://spm.du.ac.in> or may obtain from the college on all the working days between 10 am to 3 pm
19. The quotation should be sealed cover & super scribed with the words "Quotation for Repair and renovation in Room no-60,61,64,65,58,55 " and should reach at Shyama Prasad Mukherji College for women, Road no 57 west Punjabi bagh, New delhi-110026 by hand on or before 20/09/2023 by 3.00 pm
20. The undersigned has the right to increase or decrease the quantity of all or any items and also reserve the right to cancel the quotation at any time.

  
Principal



**SHYAMA PRASAD MUKHERJI COLLEGE FOR WOMEN****Bills of Quantity****Repair and renovation in Room no-60,61,64,65,58,55.**

S.NO	ITEMS	QTY	UNIT	RATE	AMOUNT
1	Providing and fixing APP (Atactic Polypropylene Polymer) modified prefabricated five layer 2 mm thick water proofing membrane, black finished reinforced with glass fibre matt consisting of a coat of bitumen primer for bitumen membrane @ 0.40 litre/sqm by the same membrane manufacture of density at 25°C, 0.87 - 0.89 kg/ litre and viscosity 70 - 160 cps. Over the primer coat the layer of membrane shall be laid using Butane torch and sealing all joints etc., and preparing the surface complete. The vital physical and chemical parameters of the membrane shall be as under : Joint strength in longitudinal and transverse direction at 23°C as 350/300 N/ 5 cm. Tear strength in longitudinal and transverse direction as 60/80N. Softening point of membrane not less than 150°C. Cold flexibility shall be upto -2°C when tested in accordance with ASTM, D - 5147. The laying of membrane shall be got done through the authorised applicator of the manufacture of membrane. 14.89.1 2mm (for corrugated roof sheets) sqm 445.80	100	Sqm		
2	Demolishing brick tile covering in terracing including stacking (demolishing carefully and stacking at site for re-use) of serviceable material and disposal of unserviceable material within 50 metres lead.	195	Sqm		
3	Demolishing mud phaska in terracing and disposal of material (stacking at site for re-use) within 50 metres lead.	22	Cum		



4	Re-fixing and laying 10 cm thick (average) mud phaska of damped brick earth on roofs laid to slope consolidated and plastered with 25 mm thick mud mortar mixed with bhusa @ 35 kg per cum of earth and gobri leaping with mix 1:1 (1 clay : 1 cow dung) and covered with flat tile bricks ( OLD TILES USED), grouted with cement mortar 1:3 (1 cement : 3 fine sand) mixed with 2% of integral water proofing compound by weight of cement and finished neat.	195	Sqm		
5	Providing and fixing Dr fixit chemical coating URP 301 mix with cement. The surface clean with fresh water and apply chemical coating.	195	Sqm		
6	Providing gola 75x75 mm in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 stone aggregate 10 mm and down gauge), including finishing with cement mortar 1:3 (1 cement : 3 fine sand) as per standard design : 12.21.1 In 75x75 mm deep chase metre	65	Mtr		

*Sadhna*  
PRINCIPAL