

**SHYAMA PRASAD MUKHERJI COLLEGE
UNIVERSITY OF DELHI
PUNJABI BAGH (WEST), NEW DELHI – 110026**

Ref : No. SPMC/Quotation/155

Date : 18-04-24

NOTICE.

Sealed quotations are invited for the civil work in the college. You are requested to quote your lowest rates for the following work in the college.


Name of the Project : Kota Flooring at Office Staircase

S. No.	Items	Qty	Unit	Rate	Amount
1	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) : 11.26.1 25 mm thick .	65	Sqm		
2	Kota stone slabs 20 mm thick in risers of steps, skirting, dado and pillars laid on 12 mm (average) thick cement mortar 1:3 (1 cement: 3 coarse sand) and jointed with grey cement slurry mixed with pigment to match the shade of the slabs, including rubbing and polishing complete.	10	Sqm		
3	Extra for Kota stone/ sand stone in treads of steps and risers using single length up to 1.05 metre.	65	Sqm		
4	Mirror polishing on marble work/Granite work/stone work where ever required to give high gloss finish complete.	75	Sqm		
5	Providing edge moulding to 18 mm thick marble stone counters, Vanities etc., including machine polishing to edge to give high gloss finish etc. complete as per design approved by Engineer-in-Charge. 8.3.1 Marble work .	70	mtr		
6	Dismantling stone slab flooring laid in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50 metres lead.	70	Sqm		

7	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	3	Cum		
	Total				

Conditions :

1. The Last date of submission of quotation is 10th May 2024.
2. Your rates must be inclusive of GST.
3. The college will deduct 1% towards electricity and water charges
4. You have to complete the work within two weeks of receipt of work order failing which penalty at 1.5% per month for delay of work to be computed on per day basis and levied on the contractor for delay of work.
5. Quotation envelop should be sealed and super-scribed as "Kota Flooring at Office Staircase"
6. The quantities can be increased or decreased according to requirements.
7. Please send your quotation by post or by hand
8. Right of acceptance of any quoted rates is reserved with the undersigned.
9. It is the sole discretion of the college to buy the items according to its requirement.
10. Your quotation rates will be valid for one year from the date of opening.


Prof. Sadhna Sharma
Principal (Officiating)